Abstract of estimate of quantities for Raising the weir of Thuraganur Tank, Reg. No. 63 of Kunigal Taluk.

Sl. No.	Items of works	Unit	Quantity
	Bund at R. L. 59·00.		
1	Earthwork to bund, including watering, consolidation, etc., complete.	C.yd.	4166
2	Turfing including watering, till it takes root	S.yd.	5661
3	Jungle clearing over the bund	Lump sum	Rupees
4	Removing and refixing the old grade stones, including painting with white lead and figuring with Japan, etc., complete.	Each	as per execution
4a	Providing and fixing new grade stones as per approved design, including painting with white lead and figuring with Japan, etc., complete.	,,	,
5	New rough stone work for revetment including jelly filling, wedging and lead of 3 miles, etc., complete.	C.yd.	227
6	Removing and resetting the old rough stone revetment, including new jelly.	,,	200
	Sluice.		
1	Earthwork cut opening the bund	C.yd.	as per execution
1(a)	Earthwork and using earth for ring bund if necessary ..	,,	,,
2	Earthwork refilling including watering, consolidation, etc., complete.	,,	,,
2(a)	Removing earth used for ring bund and refilling the cut portion, including watering, consolidation, etc., complete.	,,	,,
3	Sundry repairs to sluice	Lump sum	Rupees
	Waste weir at R. L. 54·50.		
1(a)	Earthwork excating foundation for skin wall and using soil for bund.	C.yd.	as per execution
(b)	Removing the existing rough stone apron for building slabbed apron, including the stacking of old materials.	,,	,,
2	Burnt brick in surki mortar	C.ft.	2177
3	Plastering with surki mortar	Sqr.	25·41
4	Removing and refixing the slabs of body wall, in surki mortar	S.ft.	as per execution
5	Providing and fixing bond stones (6" thick) between skin wall and body wall.	,,	,,
6	Burnt stone jelly concrete in surki mortar	C.ft.	906
7	Providing and fixing burnt stone slabs 6" thick, dressed ...	S.ft.	2567
8	Old rough stone work, rebuilding apron with available stones at site.	C.yd.	134
9	Pointing with cement	Sqr.	25·97

V. V. PATANKAR,
Executive Engineer.

MYSORE DISTRICT.

Dated 28th September 1929.

CORRECTION SLIP.

In the notification for the sale of right of collecting and removing lops and tops of trees of the Forests of the Hunsur Range published on page 1073 of Part VI of the *Mysore Gazette*, dated 25th September 1929, against Dodharve, Mavkal, Anechowkur and Kachavanahalli coupes for the date "22-10-29", "read 21-10-29".

H. S. NARAYANA RAO,
District Forest Officer.